

1993

OSCODA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 3 Pg. 154

FILED  
At 12:01 o'clock P.M.  
Date 12-6 19 93

Clerk/Register of Deeds  
Register of Deeds Stamp & Filer Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Marvin E. Myers, in a field survey on Nov 11, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Dec. 1839 Coon Mon. - Post WIT: 4" Spruce Pine N34°E 15 lks. 4" Spruce Pine S35°W 11 lks.	Consumers Power Company Oct. 1967 Mon. - Set "T" WIT: Nail & Blaze 5" J.Pine S. 26.00' Nail in 8" J.Pine SW 25.00' Nail in 6" J.Pine NE 38.32' Nail in 6" J.Pine SE 40.73'	L.1, pg.163 DNR - July 1975 P.S. 10068 Mon. - replaced "T" Iron with DNR Mon. WIT: 6" J.Pine S70°E 40.70' 6" J.Pine S03°W 26.00'
G.D. Henning May 1940		Walker Survey Feb. 1992 Mon. - DNR

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Dept of Conservation Std. Monument. Verified location by measurement to accessories and corners of record and accepted as the best available evidence of the reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Monument - Left Department of Conservation Monument in place.  
Witnesses: PK nail S. face 2" J. Pine S65°E 42.80'  
Pk nail in E. face 2" J. Pine S30°W 57.04'  
PK nail in E. face 4" J. Pine N08°W 41.65'  
PK nail in SE face 4" J. pine N42°E 97.63'  
Centerline of E-W Trail Road Due North 8'±



Signed by Marvin E. Myers Date Nov 11, 1993

Surveyor's Michigan License No. 31600  
Date approved Oct 25, 1993 Oscoda County Peer Group