

1993

OSCODA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 3 Pg 156

For corners in COMMISSION

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

**FILED**  
At 12:03 o'clock PM  
Date 12-6 19 93

Clerk/Register of Deeds  
Oscoda County, Michigan  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on Nov 16, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Dec. 1839 Coon  
Mon. - Post  
WIT: 22" W.Pine S29°E 14 lks.  
10" Y.Pine N82°E 25 lks.

DNR July 1975 K. Ostling  
Mon- Notes monument in place from previous survey

DNR - Schaaf  
Mon. - Set from original BTS.  
WIT: 20" R.Pine S73°E 84 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Monument. Verified position by measurement to accessories and corners of record and accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservation Dept. Mon.  
WIT: P.K. nail E. 4" S30°E 13.30'  
P.K. nail N. 4" Balsam S53°W 4.47'  
P.K. nail SW 8" N34°W 13.27'  
P.K. nail S 12" R.Pine N58°E 43.37'



Signed by Marvin E. Myers Date Dec 6, 1993

Surveyor's Michigan License No. 31600  
Date approved DEC 2, 1993 Oscoda County Peer Group