

1993

OSCODA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Liber 3 Pg 158

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>A-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED  
At 12:05 o'clock P M  
Date 12-6 19 93

Clerk/Register of Deeds  
Register of Deeds, State of Michigan File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on November 11, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Dec. 1839 Coon	DNR - July 1953 Schaaf
WIT: 14" Y.Pine N38°E 17 lks.	Mon. -
16" Y.Pine S19°E 88 lks.	WIT: 8" J.Pine N35°E 9 lks.
	8" J.Pine S43°E 37 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Std. Monument with 1 1/2" Pipe with concrete base (typical Schaaf monument) lying along side on surface. Verified position by measurement to accessories and corners of record and accepted as the best available evidence of the re-establishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservation Dept. Mon.  
WIT: P.K. nail W. 3" Maple N01°W 19.07'  
P.K. nail NW 4" Maple N50°E 17.66'  
P.K. nail SW 11" J.Pine S38°E 25.12'  
P.K. nail E. 6" Oak West 15.88'



Signed by Marvin E. Myers Date Dec 6, 1993

Surveyor's Michigan License No. 31600

DATE October 25, 1993 PEER GROUP APPROVAL