

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Oscoda <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>A-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Liber 3 Pg 160

FILED
At 12:07 o'clock PM
Date 12-6 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Marvin E. Myers, in a field survey on November 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Dec. 1839 Coon Mon. - Post WIT: 24" Y.Pine N49½°E 58 lks. 30" Y.Pine S37°E 19 lks.	DNR - Schaaf Mon. - WIT: 6" J.Pine S85°W 9 lks. 8" J.Pine S89°E 10 lks. (Found stumps)
---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Monument. Verified position by measurement to accessories and corners of record and accepted as the best available evidence of the re-establishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservation Dept. Mon.
WIT: P.K. nail in S. of blazed 10" J.Pine S84°E 7.55'
P.K. nail in W. 3" J.Pine S14°E 14.46'
P.K. nail in NW 4" J.Pine S58°W 11.09'
P.K. nail in SW 9" J.Pine N56°W 44.44'



Signed by Marvin E. Myers

Date Dec 6, 1993

Surveyor's Michigan License No. 31600

DATE October 25, 1993

PEER GROUP APPROVAL