

1992

OSCODA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Commission Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 1E	A - 12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Liber 3 Pg. 161

FILED
At 12:08 o'clock P M
Date 12-6 19 93

Clerk/Register of Deeds
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Marvin E. Myers, in a field survey on November 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

DNR - July 1970 P.S. 10068
Mon. - DNR Mon.
WIT: 6" J.Pine S41°E 17.60'
7" J.Pine N23°E 28.60' (Fd. both BT's)
Cor. for 36 T28N, R1W is North 75.70'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Monument. Verified position by measurement to accessories and corners of record and accepted as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservation Dept. Mon.
WIT: nail in same 9" J.Pine S41°E 17.90'
nail E. 5" Poplar 7.56'
nail S. 10" Oak 12.15'
nail E. 10" J.Pine 46.33'
332' South to swamp



Signed by Marvin E. Myers Date Dec 6, 1993

Surveyor's Michigan License No. 31600

DATE October 25, 1993 PEER GROUP APPROVAL