

RECORDED

OSCODA COUNTY REMONUMENTATION

1893

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OSCODA  
Oscoda (County)

Located In: Corner Code #/

1. Public Land Survey	T	28N	R	1E	A-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Liber 3 Pg 162

FILED

At 12:09 o'clock P.M.  
Date 12-6 19 93

Clerk/Register of Deeds  
Oscoda County, Michigan  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Marvin E. Myers, in a field survey on November 22, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO - Mon. June 1839 Clason  
WIT: 18" Cedar S48 1/2°E 59 lks.  
16" Cedar N14 1/2°E  
DNR Aug. 1953 Shaaf  
Mon. -  
WIT: 10" J.Pine S58°W 48 lks.


GLO  
Mon. -  
8" Spruce N75°W 28 lks.  
10" Cedar S10°W 39.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Conservation Dept. Monument. Verified position by measurement to accessories and corners of record and accepted as the best available evidence of the re-establishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Mon. - Left in place Std. Conservation Dept. Monument  
WIT: P.K. nail S. 4" J.Pine N88°E 61.87'  
P.K. nail W. 7" Poplar S18°E 35.94'  
P.K. nail SE 4" J.Pine S86°W 16.50'  
P.K. nail SW 6" Poplar N37°W 12.70'



Signed by Marvin E. Myers Date Dec 6, 1993  
Surveyor's Michigan License No. 31600

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

DATE October 25, 1993 PEER GROUP APPROVAL