

1993

1993 OSCODA COUNTY RE-MONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

OSCODA  
(County)

Located In:

Corner Code #

GREENWOOD TWP.

1. Public Land Survey

T 28N R 1E

C-2

T 28N R 1E

C-2

T R

T R

2. Property Controlling  
in Section

S T R

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Liber 3 Pg 167

FILED

At 1:19 o'clock P M

Date 12-8 1993

Clerk/Register of Deeds  
Oscoda County, Michigan  
Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on September - October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-1 NE Cor. Sec. 6 & NW Cor. Sec. 5, T.28 N., R.1 E.

C-2 1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.

Orig. Post by W. Coon - Dec. 1839  
S.62°E. 17 lks (11.22') Aspen  
S.40°W. 11 lks ( 7.26') Y. Pine  
1967 Un-Rec. Sur. by H. Dorsey for Co. Pwr. Co. - Fnd.  
1/2" Iron & Well Pt. 34.32' E of 1/2" Iron @  
Cor. C-13, T29N,R1E. - No Wit.  
1975 Act 132 Sur. by G. Henning Rec. L.2, Pg 177-181  
Fnd 1/2" Iron 36.6' E. of Cor. C-13 No Wit.  
ACT 74 - Rec. Bk. 3, Pg 27 - C.Johnson - Fnd Rec Iron  
Replaced with DNR Pipe & Cap & R.T. Post S23°W-34.3'-  
4" R. Pine S11°E - 25.7' - 5" W. Birch - June 1987

Orig. Post by W. Coon - Dec. 1839  
S.31°E. - 4 lks ( 2.64') Aspen  
N.32°W. - 7 lks ( 4.62') Birch  
1967 Un-Rec. Sur. by H. Dorsey for Co. Pwr. Co. - Does  
not indicate any Cor. Fnd. or show any Wit.  
ACT 74 - Not Rec. - Obtained from Grayling DNR Office  
C.Johnson - Fnd. 3/4" Pipe - Replaced with DNR Pipe  
& Cap - S55°W 26.1' 7" W. Pine N9°W 42.8' 6" R Pin  
June 1987.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1 NE Cor. Sec. 6 & NW Cor. Sec. 5, T.28 N., R.1 E.

C-2 1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.

Fnd. Rec. DNR Pipe & Cap with 1/2" Iron on W. Sd.  
Fnd. Johnson Blaze - S.23°W. - 34.3' - 4" R. Pine  
Fnd. Henning Tag - S.35°E. - 15.21' - 24" W. Pine

Fnd. Rec. DNR Pipe & Cap  
Fnd Johnson Blaze - S.55°W - 26.1' - 7" W. Pine  
Fnd Johnson Blaze - N.09°W - 42.8' - 6" R. Pine  
Fnd Old Blaze - No Tag - S.20°W. - 10.0' - 8" Oak

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP.  
NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by the Oscoda County Peer Review on October  
25, 1993, as the best available evidence of the re-  
establishment of the original corner

Approved by the Oscoda County Peer Review on October  
25, 1993, as a careful and faithful establishment of  
the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 NE Cor. Sec. 6 & NW Cor. Sec. 5, T.28 N., R.1 E.

C-2 1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.

Fnd. Rec. DNR Pipe & Cap (Bk. 3, Pg. 27)  
S.35°E.- 15.21' - Fnd. Henning Tag N. Sd. 24" W. Pine  
S.23°W.- 34.33' - Set Tag E. Sd. 6" W. Pine  
N.80°W.- 23.88' - Set Tag S. Sd. E. Gate Post  
N.45°W.- 50.44' - Set Tag NE Sd. 15" Pine  
West - 36.57'(M)- Fnd 1/2" Iron @ Cor. C-13 T29N,R1E  
R.T. Post Alongside Corner

Fnd. Rec. DNR Pipe & Cap (Grayling DNR Office)  
Cor. is 190' W. of the C.L. of a N-S 2 Track Trail  
S.80°E. - 26.27' - Set Tag N. Sd. 15" Oak  
S.20°W. - 10.25' - Set Tag E. Sd. 8" Oak  
S.55°W. - 26.37' - Set Tag SE Sd. 8" W. Pine  
N.09°W. - 43.26' - Set Tag W. Sd. 8" R. Pine  
R.T. Post Alongside Corner

NOTE: All witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King

Date Dec. 7, 1993

Surveyor's Michigan License No. 25852

