

**1993 OSCODA COUNTY RE-MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OSCODA
(County)

Located In: GREENWOOD TWP. Corner Code # C-1

- | | | |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>C-1</u> |
| | T <u>28N</u> R <u>1E</u> | <u>C-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Liber 3 Pg 167

FILED

At 1:19 o'clock P M
Date 12-8 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on September - October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|---|
| C-1 <u>NE Cor. Sec. 6 & NW Cor. Sec. 5, T.28 N., R.1 E.</u>
Orig. Post by W. Coon - Dec. 1839
S.62°E. 17 lks (11.22') Aspen
S.40°W. 11 lks (7.26') Y. Pine
1967 Un-Rec. Sur. by H. Dorcey for Co. Pwr. Co. - Fnd. 1/2" Iron & Well Pt. 34.32' E of 1/2" Iron @ Cor. C-13, T29N,R1E. - No Wit.
1975 Act 132 Sur. by G. Henning Rec. L.2, Pg 177-181
Fnd 1/2" Iron 36.6' E. of Cor. C-13 No Wit.
ACT 74 - Rec. Bk. 3, Pg 27 - C.Johnson - Fnd Rec Iron Replaced with DNR Pipe & Cap & R.T. Post S23°W-34.3'-4" R. Pine S11°E - 25.7' 5" W. Birch - June 1987 | C-2 <u>1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.</u>
Orig. Post by W. Coon - Dec. 1839
S.31°E. - 4 lks (2.64') Aspen
N.32°W. - 7 lks (4.62') Birch
1967 Un-Rec. Sur. by H. Dorcey for Co. Pwr. Co. - Does not indicate any Cor. Fnd. or show any Wit.
ACT 74 - Not Rec. - Obtained from Grayling DNR Office C.Johnson - Fnd. 3/4" Pipe - Replaced with DNR Pipe & Cap - S55°W 26.1' 7" W. Pine N9°W 42.8' 6" R Pine June 1987. |
|---|---|

- | | | |
|---|---|---|
| B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: | C-1 <u>NE Cor. Sec. 6 & NW Cor. Sec. 5, T.28 N., R.1 E.</u>
Fnd. Rec. DNR Pipe & Cap with 1/2" Iron on W. Sd.
Fnd. Johnson Blaze - S.23°W. - 34.3' - 4" R. Pine
Fnd. Henning Tag - S.35°E. - 15.21' - 24" W. Pine | C-2 <u>1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.</u>
Fnd. Rec. DNR Pipe & Cap
Fnd Johnson Blaze - S.55°W - 26.1' - 7" W. Pine
Fnd Johnson Blaze - N.09°W - 42.8' - 6" R. Pine
Fnd Old Blaze - No Tag - S.20°W. - 10.0' - 8" Oak |
|---|---|---|

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by the Oscoda County Peer Review on October 25, 1993, as the best available evidence of the re-establishment of the original corner

Approved by the Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| C-1 <u>NE Cor. Sec. 6 & NW Cor. Sec 5, T.28 N., R.1 E.</u>
Fnd. Rec. DNR Pipe & Cap (Bk. 3, Pg. 27)
S.35°E.- 15.21' - Fnd. Henning Tag N. Sd. 24" W. Pine
S.23°W.- 34.33' - Set Tag E. Sd. 6" W. Pine
N.80°W.- 23.88' - Set Tag S. Sd. E. Gate Post
N.45°W.- 50.44' - Set Tag NE Sd. 15" Pine
West - 36.57'(M)- Fnd 1/2" Iron @ Cor. C-13 T29N,R1E R.T. Post Alongside Corner | C-2 <u>1/4 Cor. Common to Sec. 5 & 6, T.28 N., R.1 E.</u>
Fnd. Rec. DNR Pipe & Cap (Grayling DNR Office)
Cor. is 190' W. of the C.L. of a N-S 2 Track Trail
S.80°E. - 26.27' - Set Tag N. Sd. 15" Oak
S.20°W. - 10.25' - Set Tag E. Sd. 8" Oak
S.55°W. - 26.37' - Set Tag SE Sd. 8" W. Pine
N.09°W. - 43.26' - Set Tag W. Sd. 8" R. Pine
R.T. Post Alongside Corner |
|--|---|

NOTE: All witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King
Surveyor's Michigan License No. 25852

Date Dec. 7, 1993

