

1993

1993 OSCODA COUNTY RE-MONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION

Table with columns: OSCODA (County), Located In: GREENWOOD TWP., Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Liber 3 Pg. 170

FILED

At 1:22 o'clock P M Date 12-8 19 93

Clerk/Register of Deeds Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, Frederick J. King, in a field survey on September - October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. Two dots are marked at grid intersections (7,19) and (8,20).

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-7 Cor. Common to Sec. 17, 18, 19 & 20, T.28 N., R.1 E. C-8 1/4 Cor. Common to Sec. 19 & 20, T.28 N., R.1 E. Orig. Post by W. Coon - Dec. 1839... 1971 - Act 132 Sur. Rec. L.1, Pg. 13-15 by N. Caldwell Meas. entire Sec. 20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-7 Cor. Common to Sec. 17, 18, 19 & 20, T.28 N., R.1 E. C-8 1/4 Cor. Common to Sec. 19 & 20, T.28 N., R.1 E. Fnd. Rec. Oscoda County Pipe & Cap No Old Witnesses Found Meas. E. to Cor. D-7 - 2649.1'(M) 2649.2'(R) per Co. Pwr. Co. Surveys.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the position of the corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7 Cor. Common to Sec. 17, 18, 19 & 20, T.28 N., R.1 E. C-8 1/4 Cor. Common to Sec. 19 & 20, T.28 N., R.1 E. Fnd. Rec. Oscoda County Pipe & Cap (L.1, Pg 13-15 Sur) Corner is 10' S. of C.L. of Henning Rd. (Dirt Rd.) N.35°E. - 64.58' - Set Tag SW Sd. 20" Twin Oak S.60°E. - 11.27' - Set Tag S. Sd. 16" J. Pine S.15°E. - 9.37' - Set Tag W. Sd. 10" J. Pine N.40°W. - 42.71' - Set Tag SW Sd. 16" Twin J. Pine Set Treated R.T. Post Alongside Corner

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King Date Dec. 7, 1993

Surveyor's Michigan License No. 25852

