

**1993 OSCODA COUNTY RE-MONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

OSCODA

(County)

Located In:

GREENWOOD TWP.

Corner Code #

- |                                       |                          |            |
|---------------------------------------|--------------------------|------------|
| 1. Public Land Survey                 | T <u>28N</u> R <u>1E</u> | D-5        |
|                                       | T <u>28N</u> R <u>1E</u> | <u>D-7</u> |
|                                       | T _____ R _____          | _____      |
|                                       | T _____ R _____          | _____      |
| 2. Property Controlling in Section    | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____  | _____      |
|                                       | S _____ T _____ R _____  | _____      |
| 4. Lot No. _____, Recorded Plat _____ |                          |            |
| 5. Private Claims _____               |                          |            |

Liber 3 pg 174

**FILED**

At 1:26 o'clock P M

Date 12-8 1993

Clerk/Register of Deeds  
Oscoda County, Michigan  
Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		●										
6	18	17	16	15	14	13						
7		●										
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

**D-5 1/4 Cor. Common to Sec. 8 & 17, T.28 N., R.1 E.**  
Orig. Post by W. Coon - Dec. 1839  
S.14°E.- 3 lks (1.98') Spr. Pine  
N.10½°W- 21 lks (13.86') Spr. Pine  
1940 - Un-Rec. Sur. by G. Henning - Meas Sec. 7,8,17 & 18  
Set Oak Post: N.26°W.- 85½ lks (56.43') - 5" B. Oak  
S.54½°W.- 55 lks (36.30') - 8" W. Oak  
1967 - Un-Rec. Sur. by H. Dorcey for Co. Pwr. Co. -  
Fnd. & Accepted a 1" Pipe N - 5.35' - 6" W. Oak,  
NNW- 31.21' - 8" W. Oak, SSW- 26.85' - 8" W. Oak  
1981 - Un-Rec. Sur. by D. Marlatt-Fnd. 1½" Well Pt. &  
1" Pipe, S60°W-35.7'-12"Oak, S.35°E-37.0'-6"Oak  
S31°W-26.96'-10"Oak **NO ACT 74 RECORDED**

**D-7 1/4 Cor. Common to Sec. 17 & 20, T.28 N., R.1 E.**  
Orig. Post by W. Coon - Dec. 1839  
N1°E - 82 lks (54.12') Y. Pine  
S4°W - 65 lks (42.90') Y. Pine  
1940 - Un-Rec. Sur. by G. Henning - Meas Sec. 7,8,17 & 18  
Did not establish or wit. this corner  
1967 - Un-Rec. Sur. by H. Dorcey for Co. Pwr. Co. - Fnd.  
Sq. Wd. Post & Replcd with T Iron, SW-32.00-10"  
J.Pine, SE-17.51'-8" J.Pine, NE-36.25'-8" J.Pine  
1971 - Act 132 Sur.- Rec. L.1, Pg. 13-15 by N. Caldwell  
Meas entire Sec. 20- Did not indicate cor. evi-  
dence fnd. or wit.  
**NO ACT 74 RECORDED FOR THIS CORNER**

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

**D-5 1/4 Cor. Common to Sec. 8 & 17, T.28 N., R.1 E.**  
Fnd. Rec. 1" Pipe with R.T. Post  
No Record Witnesses Found  
Meas. East 2659.70' (Rec-2659.79') to Cor. E-5  
Agrees with H. Dorcey Survey.

**D-7 1/4 Cor. Common to Sec. 17 & 20, T.28 N., R.1 E.**  
Fnd. Oscoda County Pipe & Cap with R.T. Post  
No Record Witnesses Found  
Meas. East 2649.55' (Rec-2649.62') to Cor. E-7  
Agrees with H. Dorcey Survey.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the position of the corner.

Approved by Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the position of the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

**D-5 1/4 Cor. Common to Sec. 8 & 17, T.28 N., R.1 E.**  
Set Oscoda County Pipe & Cap @ 1" Pipe position  
Corner is ±25' S. of C.L. of Williams Rd. (Dirt Rd.)  
S.75°E. - 9.54' - Set Tag N. Sd. 20" Oak  
S.10°E. - 10.88' - Set Tag W. Sd. 16" Oak  
S.40°W. - 11.45' - Set Tag SE Sd. 6" Maple  
N.65°W. - 10.90' - Set Tag NE Sd. 24" Oak

**D-7 1/4 Cor. Common to Sec. 17 & 20, T.28 N., R.1 E.**  
Fnd. Oscoda County Pipe & Cap  
Corner is ±15' S. of C.L. of Henning Rd. (Dirt Rd.)  
N.85°E. - 11.03' - Set Tag N. Sd. 4" Oak  
S.10°W. - 0.98' - Set Tag W. Sd. Fnc. Cor. Post  
S.75°W. - 11.01' - Set Tag N. Sd. 5" Maple  
R.T. Post Alongside Corner.

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King

Date Dec. 7, 1993

Surveyor's Michigan License No. 25852

