

**1993 OSCODA COUNTY RE-MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA

(County)

Located In:

GREENWOOD TWP.

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------|
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>D-9</u> |
| | T <u>28N</u> R <u>1E</u> | <u>D-11</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Liber 3 pg 175

FILED

At 1:27 o'clock P M

Date 12-8 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Frederick J. King, in a field survey on September - October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9		●										
10	30	29	28	27	26	25						
11		●										
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-9 1/4 Cor. Common to Sec. 20 & 29, T.28 N., R.1 E.
Orig. Post by W. Coon - Dec. 1839
N.30°W.- 5 lks (3.30') Aspen
S.28°E.- 10 1/2 lks (6.93') Aspen
1971 - Act 132 Sur. Rec. L.1, Pg. 13-15 by N. Caldwell
Meas Entire Sec. 20 - No Cor. Ref. - No Wit.
ACT 74 Rec. Bk.1, Pg. 43 - Oscoda County Pipe & Cap set
by N. Caldwell (Aug. 1971) N.40°E.-32.1'-12" J.P.
S.30°E.-12.3'-10" J.Pine, S.70°W.-16.35'-12" J.P.

D-11 1/4 Cor. Common to Sec. 29 & 32, T.28 N., R.1 E.
Orig. Post by W. Coon - Dec. 1839
S.39°W.- 5 lks (3.30') Tam.
N.39°E.- 12 lks (7.92') Tam.
1962 - Un-Rec. Sur. by K. Ostling- Meas. entire Sec.
32-Set DNR Pipe & Cap by Prop. Meas., on line
& at Mid-Point between Cor. C-11 & E-11
DNR Witness Sheet - Rec. Bk. 2, Pg. 200 - Ostling
States Evidence of Prev. Cor. Not Fnd.
Cor. Set faces old Blzd Stmp - possible BT
South - 22.3' - 8" J. Pine
West - 46.5' - 7" J. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9 1/4 Cor. Common to Sec. 20 & 29, T.28 N., R.1 E.
Fnd. Rec. Oscoda County Pipe & Cap with R.T. Post
Fnd. Caldwell Blaze- S.30°E.-12.3'- 10" J. Pine
Fnd. Caldwell Blaze- S.70°W.-16.35'-12" J. Pine

D-11 1/4 Cor. Common to Sec. 29 & 32, T.28 N., R.1 E.
Fnd. Rec. DNR Pipe & Cap
Area has been clear cut - Road has been widened &
Pwr. Line Constructed - All Ostling Wit. Gone.
Meas. E. 2637.4' (Rec. 2636.9) to Cor. E-11 & Meas.
W. 2637.4' (Rec. 2636.9') to Cor. C-11 - Cor. is at
Mid Point as indicated on Ostling Survey.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP.
NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP.
NOTES ARE FRADULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by Oscoda County Peer Review on October 25,
1993, as a careful and faithful establishment of the
position of the corner.

Approved by Oscoda County Peer Review on October 25,
1993, as a carefule and faithful establishment of the
position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 1/4 Cor. Common to Sec. 20 & 29, T.28 N., R.1 E.
Fnd. Rec. Oscoda County Pipe & Cap
Corner is in E-W Single Strand Fence
Corner is ±150' W. of C.L. of N-S 2 Track Trail:
East - 32.44' - Set Tag N. Sd. 20" J. Pine
S.30°E. 12.52' - Set Tag NE Sd. 18" J. Pine
S.70°W. 16.38' - Set Tag NW Sd. 20" J. Pine
West- 26.90' - Set Tag S. Sd. 18" J. Pine
R.T. Post Alongside Corner

D-11 1/4 Cor. Common to Sec. 29 & 32, T.28 N., R.1 E.
Fnd. Rec. DNR Pipe & Cap
Corner is ±30' S. of C.L. of Farrington Rd. (Dirt Rd)
Corner is ±11' NW of C.L. of 2 Track Trail running SW
S.70°E. - 24.41' - Set Tag SW Sd. 10" J. Pine
S.55°W. - 29.03' - Set Tag SE Sd. 8" Oak
N.60°W. - 106.74' - Set Tag S. Sd. Pwr. Pole
N.15°W. - 86.31' - Set Tag E. Sd. 6" Oak
Set Treated R.T. Post Alongside Corner

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Cap #25852

Signed by Frederick J. King

Date Dec. 7, 1993

Surveyor's Michigan License No. 25852

