

COMMISSION

1993 OSCODA COUNTY RE-MONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA (County) Located In: GREENWOOD TWP. Corner Code #: E-13
1. Public Land Survey T 28N R 1E
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Liber 3 pg 176

FILED

At 1:28 o'clock P.M

Date 12-8 1993

Clerk/Register of Deeds Oscoda County, Michigan Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on September - October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

- D-13 South 1/4 Cor., Sec. 32, T.28 N., R.1 E. Orig. Post by Lewis Clawson - 1839 S.72 1/2 E. - 7.06 lks (4.66') Y. Pine
E-13 SE Cor. Sec. 32 & SW Cor. Sec. 33, T.28 N., R.1 E. Orig. Post by Lewis Clawson - 1839 N.35 E. - 1.17 lks (0.77') Y. Pine

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-13 South 1/4 Cor., Sec. 32, T.28 N., R.1 E. Fnd. Rec. DNR Pipe & Cap with R.T. Post
E-13 SE Cor. Sec. 32 & SW Cor. Sec. 33, T.28 N., R.1 E. Fnd. Rec. 1 1/2" Pipe @ Cor. E-13

Approved by Oscoda County Peer Review on October 25, 1993, as the best available evidence of the re-establishment of the original corner,

Approved by Oscoda County Peer Review on October 25, 1993, as a perpetuation of the original government corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-13 South 1/4 Cor., Sec. 32, T.28 N., R.1 E. Fnd. Rec. DNR Pipe & Cap (Bk. 2, Pg. 202) Corner is 1/2 S. of C.L. of Town Hall Rd. (Dirt Rd.)
E-13 SE Cor. Sec. 32 & SW Cor. Sec. 33, T.28 N., R.1 E. Fnd. Rec. 1 1/2" Pipe (Bk. 2, Pg. 203) Corner is 1/2 S. of C.L. of Town Hall Rd. (Dirt Rd.)

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King Surveyor's Michigan License No. 25852

Date Dec 7, 1993

