

**1993 OSCODA COUNTY RE-MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OSCODA COUNTY

<u>OSCODA</u> (County)	Located In: GREENWOOD TWP.	Corner Code # E-6
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>E-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Liber 3 Pg 180

FILED
At 1:32 o'clock PM
Date 12-8 1993

Clerk/Register of Deeds
Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on September, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6 1/4 Cor. Common to Sec. 16 & 17, T.28 N., R.1 E.

Orig. Post by W. Coon - Dec. 1839
S.33°W.-16 lks (10.56') Spr. Pine
N.37°W.-28 lks (18.48') Spr. Pine
1915 - Sur. by C.O. Seeley - Meas. Entire E Tier
Set 5/8" Iron - S.71½°W.-26 lks (17.16') Pine
1940 - Un-Rec. Sur. by G. Henning - Set 3/4" Pipe
Fnd. Seeley Blz.- S.25½°W.-55 lks (36.30') of
Pipe Set, N.58½°W.-17 lks (11.22') J. Pine
S.42°E.-77 lks (50.82') J. Pine

1967 - Un-Rec. Sur. by H. Dorsey for Co. Pwr. Co.
Fnd. Henning Pipe, S- 74.0'- P. Pole, W- 44.01'-
8" J. Pine, NW- 49.15'- 8" J. Pine
1981 - Un-Rec. Sur. by D. Marlatt - Fnd. Rec. Pipe
N.73°W.- 52.58'- 12" Oak, S.70°W.- 52.95'- 9" Oak
N.85°E.- 52.25'- 10" Oak
NO ACT 74 RECORDED FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 1/4 Cor. Common to Sec. 16 & 17, T.28 N., R.1 E.

Fnd. Rec. 3/4" Pipe
Fnd. Rec. Dorsey Wit. - South - 74.0'- Pwr. Pole
Fnd. Rec. Marlatt Wit.- N.85°E.- 52.25'- 10" Oak
Fnd. Rec. Marlatt Wit.- N.73°W. - 52.58' - 10" Oak

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRAUDULANT-NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by the Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 1/4 Cor. Common to Sec. 16 & 17, T.28 N., R.1 E.

Set Oscoda County Pipe & Cap @ 3/4" Pipe position
Corner is 126' E. of C.L. of Neumann Rd. (Dirt Rd.)
Corner is in line with Overhead N-S Pwr. Line
N.50°E.- 68.76' - Set Tag NW Sd. 10" Map.
S.85°E.(R-N85°E) - 53.55' - Set Tag N. Sd. 12" Oak
South - 74.57' - Set Tag E. Sd. Pwr. Pole
N.80°W.(R-N73°W) - 53.03' - Set Tag N. Sd. 12" Oak
Set Treated R.T. Post Alongside Corner

NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King Date Dec 7, 1993
Surveyor's Michigan License No. 25852

