

1993 OSCODA COUNTY RE-MONUMENTATION

1993

1993 OSCODA COUNTY RE-MONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

Liber 3 Pg 184

For corners in

<u>OSCODA</u> (County)	Located In: <u>GREENWOOD TWP.</u>	Corner Code # <u>E-12</u>
1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
At 1:36 o'clock PM
Date 12-8 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

I, Frederick J. King, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12 1/4 Cor. Common to Sec. 32 & 33, T.28 N., R.1 E.
Orig. Post by W. Coon - Dec. 1839
S52°W- 7 lks (4.62') Tam.
N52°E- 15 lks (9.90') Tam.
1915 - Sur. by C.O. Seeley - Meas. entire E Tier
Fnd. 18" Stone Casting, N78°E- 81 lks (53.46')
Y. Pine Stmp, N23°W- 98 lks (64.68') Y. Pine Stmp
1962 - Un-Rec. Sur. by K. Ostling - Entire Sec. 32
Fnd. 1" Bar @ Fnc. Cor. - No wit.
NO ACT 74 RECORDED FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12 1/4 Corner Common to Sec. 32 & 33, T.28 N., R.1 E.
Fnd. Rec. 1" Bar @ Fnc. Cor.
Fnd. Old Blaze - N70°E - 8.0' - 12" J. Pine - No Rec.

PREVIOUS COUNTY SURVEYORS HAVE INDICATED THAT THIS TWP. NOTES ARE FRADULANT- NO EVIDENCE OF ORIGINAL SURVEY FND.

Approved by Oscoda County Peer Review on October 25, 1993, as a careful and faithful establishment of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12 Set Oscoda County Pipe & Cap @ 1" Bar position
Corner is @ Corner of Fences from N, S & W
Corner is ±30' West of N-S Overhead Pwr. Line
N.70°E. - 8.27' - Set Tag SE Sd. 12" J. Pine
S.30°E. - 61.26' - Set Tag SW Sd. Pwr. Pole
N.85°W. - 55.66' - Set Tag S. Sd. 36" Oak
N.50°W. - 50.13' - Set tag SW Sd. 30" Oak
Set Treated R.T. Post Alongside Corner



NOTE: All Witnesses Marked with Db1. Headed Nails & I.D. Tag #25852

Signed by Frederick J. King Date Dec. 7, 1993
Surveyor's Michigan License No. 25852