

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 3 pg 206

For corners in

<u>Oscoda</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>28 N</u> R <u>1 E</u>	<u>(F-1)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

FILED
 At 11:26 o'clock A M
 Date 12-17 1993

Clerk/Register of Deeds
 Register of Deeds Stamp & File Number

I, Larry G Beauregard, in a field survey on October, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

(F-1) No original corner set on Twp. line.
 Fnd. Oscoda Co. std. corner on Montmorency Oscoda Co. line set by Norman C. Caldwell P.S. #12018, Dec. 27, 1974. Fnd. record references: DNR red top post along side of cor. in good condition. No Act 74 on file.
 W 24.48' S. $\frac{1}{4}$ corner for Sec. 33, T29N, R1E, conc. mon.
 S 70° E 18" Y. Pine stp. 29.10'
 N 65° W 18" Y. Pine stp. 18.55'

Larry G. Beauregard (R.S. Scott Assoc. Inc.) in 1982 fnd. cor. and ref. mentioned above. (No Act 74 on file).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F-1) Fnd. Oscoda Co. std. Cor. 1" x 3' pipe & 3" brass cap.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F-1) N. $\frac{1}{4}$ Cor. Sec. 4, T28N, R1E
 Fnd. Oscoda Co. std. cor. 1" x 3' pipe & 3" brass cap. Accepted as a careful and faithful establishment of the position of the corner, approved by the Peer Group on Oct. 25, 1993.
 West 24.48' (R) 24.57' (M) conc. mon. S. $\frac{1}{4}$ Cor. Sec. 34, T29N, R1E
 S 70° E 29.10' (R) & (M) 18" Y. Pine stp.
 N 65° W 18.60' (R) & (M) 18" Y. Pine stp.
 N 50° E 32.88' 5" Maple

(Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12/17/93
 Surveyor's Michigan License No. 18654