

1893
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L.3 Pg 232

For corners in

Oscoda
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|---------------|
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>(H-13)</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
At 11:52 o'clock A M
Date 12-17 19 93

Clerk/Register of Deeds
Oscoda County, Michigan

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Larry G Beauregard, in a field survey on October, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(H-13) Original post set by Lewis Clawson June 1839
Aspen 6" N 38° W 18 links W. Birch 6" N 43° E 13 links
No evidence of Cor. or Wits. found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(H-13) Set std. Oscoda Co. Cor. by S.P. method on Twp. line between Rec. Sec. Corners E & W, 6" above ground.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(H-13) S. ¼ Cor. Sec. 34, T28N, R1E
Std. Oscoda Co. Cor. 1" x 3' pipe with 3" brass cap #18654 6" above ground.
Accepted as the best available evidence of the reestablishment of the original corner, approved by the Peer Group on Oct. 25, 1993.
N 70° E 31.85' 6" J. Pine
N 84° E 24.97' 7" Tamarack
S 60° E 43.32' 5" Tamarack
S 05° E 30.09' 6" Tamarack
West 17.70' ½" bar & P.S. cap #12018
N¼ Cor. Sec. 3, T27N, R1E
(Placed blaze, 20 penny spike & P.S. tag #18654) (typ)

Signed by Larry G. Beauregard Date 12/17/93
Surveyor's Michigan License No. 18654