

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>J-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

L 3 Pg. 185

FILED

At 8:35 o'clock A M
Date Dec. 14 19 93

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (J-1) N. ¼ Cor. Sec. 2, T28N, R1E.
Cor. not set with original government Survey.
No record of Cor. ever being established.
Recorded Plat Mielke Way Sub by N.C. Caldwell 12-30-70
Survey Recorded by N.C. Caldwell in Sec. 2, Nov. 5, 1973.
Survey by R.S. Scott Eng. in Sec. 35, 29-1, 8-23-74.
Survey by D.E. Marlatt Sec. 2, 28-1, 5-21-80.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (J-1) N. ¼ Cor. Sec. 2, T28N, R1E.
No evidence of corner.
Set County Mon. by extending N & S ¼ line from S ¼ through existing center of Sec. to intersection with North Section line. Corner falls 7.88' West of S ¼ Cor. Sec. 35, 29-1.


Peer Group approved as a careful and faithful establishment of the position of the corner.

Note: Previous Co. Surveyors have indicated that the original Twp. ^{SUB.} notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- (J-1) N ¼ Cor. Sec. 2, T28N, R2E
Set County Mon.
S 13° W 9" Oak 21.68'
S 72° W 13" Oak 27.32'
N 15° W 11" Oak 13.63'
S 56° E 13" Oak 50.25'
North Edge of Road.

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.



Signed by Donald E. Marlatt Date 12-13-1993

Surveyor's Michigan License No. 18660