

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|------------|---|-----------|------------|
| 1. Public Land Survey | T | <u>28N</u> | R | <u>1E</u> | <u>K-7</u> |
| | T | <u>28N</u> | R | <u>1E</u> | <u>K-8</u> |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | | |
| | S | | T | | |
| 3. Miscellaneous Property in Sec. | S | | T | | |
| | S | | T | | |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

L 3 Pg 192

FILED

At 8:42 o'clock A M

Date Dec. 14 19 93

Clerk/Registrar of Deeds

Register of Deeds Stamp & File Number

I, Donald E. Marlatt, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|--|--|
| (K-7) Cor. Comm. to Sec's 13-14-23 & 24.
Orig. Cor. set by W.R. Coon Dec. 1839.
Spr. Pine 6-N32W 9, Y. Pine 12-S38E-17.
Cor. set by Seeley Survey 1915.
Survey by G. Henning 4-8-1952.
Fnd. Seeley B.T. & Grader Blade.
Survey by Caldwell L. 1, P. 12.
Act 74 by Caldwell L. 1, P. 44.
Act 74 by Quaine L. 3, P. 134. | (K-8) ¼ Cor. Comm. to Sec's 23 & 24.
Orig. Cor. set by W.R. Coon Dec. 1839.
Spr. Pine 10-N19E-21, Spr. Pine 8-S22W-18.
Cor. set by Seeley Survey 1915.
Act 74 by Caldwell L. 1, P. 44. |
|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|--|
| (K-7) Cor. Comm. to Sec's 13-14-23 & 24.
Fnd. Grader Blade. (Seeley) | (K-8) ¼ Cor. Comm. to Sec's 23 & 24.
Fnd. Co. Mon.
S 23° E 10" J. Pine 47.0'
S 81° E 14" J. Pine 17.21' |
|---|--|

Peer Group approved as a careful and faithful establishment of the position of the corner.

Note: Previous Co. Surveyors have indicated that the original Twp. ^{SUB.} notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| (K-7) Cor. Comm. to Sec's 13-14-23 & 24.
Set Co. Mon.
S 20° E 8" Oak 47.45'
N 44° E 12" Oak 89.06'
N 41° W P. Pole 76.31'
S 89° W 12" J. Pine 76.45' | (K-8) ¼ Cor. Comm. to Sec's 23 & 24.
Fnd. Co. Mon.
S 47° E 12" J. Pine 38.62'
S 23° E 10" J. Pine 47.0'
S 81° E 14" J. Pine 17.21'
N 30° E 7" J. Pine 78.25'
N 83° W 14" Oak 74.42' |
|---|---|

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E. Marlatt

Date 12-13-1993

Surveyor's Michigan License No. 18660

