

Montmorency County Remonumentation

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

L 3 pg 193

For corners in

Oscoda (County) Located In: Corner Code #

1. Public Land Survey T 28N R 1E K-9
T 28N R 1E K-10
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. , Recorded Plat

5. Private Claims

FILED At 8:43 o'clock A.M.

Date Dec. 14 19 93

Clerk/Register of Deeds
Oscoda County, Michigan

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Donald E. Marlatt, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K-9) Cor. Comm. to Sec's 23-24-25 & 26. (K-10) 1/4 Cor. Comm. to Sec's 25 & 26.
Orig. Cor. set by W.R. Coon Dec. 1839. Orig. Cor. set by W.R. Coon Dec. 1839.
Spr. Pine 4-S60E-16. Spr. Pine 7-N52E-36.
Spr. Pine 6-N60W-21. Spr. Pine 7-S50 1/2 W-19.
Cor. set by Seeley Survey 1915. Cor. set by Seeley Survey 1915.
DNR Survey of Sec. 25. DNR Survey Sec. 25.
Act 74 by Ken Ostling L. 1, P. 172. Act 74 by Ken Ostling, L. 1, P. 173.
Consumers Power Com. Survey Oct. 1967.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K-9) Cor. Comm. to Sec's 23-24-25 & 26. (K-10) 1/4 Cor. Comm. to Sec's 25 & 26.
Fnd. DNR Mon. Fnd. DNR Mon.
N 60° E 12" J. Pine 50.6' N 24° E 10" Oak 26.48'
S 73° E 11" J. Pine 30.62' N 47° W 12" N. Pine 53.91'

Peer Group approved as a careful and faithful establishment of the position of the corner.

Note: Previous Co. Surveyors have indicated that the original Twp. notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K-9) Cor. Comm. to Sec's 23-24-25 & 26. (K-10) 1/4 Cor. Comm. to Sec's 25 & 26.
DNR Mon. D.N.R. MONUMENT.
N 60° E 12" J. Pine 50.60' S 35° E 10" Oak 64.02'
S 73° E 11" J. Pine 30.62' N 24° E 10" Oak 26.48'
S 44° W 13" J. Pine 91.26' N 4° W 8" J. Pine 40.12'
N 48° W 12" J. Pine 71.05' N 47° W 12" N. Pine 53.91'

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E Marlatt

Date 12-13-1993

Surveyor's Michigan License No. 18660

