

1833
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

L 3 pg 194

For corners in Oscoda (County) Located In: Corner Code #/

1. Public Land Survey	T <u>28N</u> R <u>1E</u>	<u>K-11</u>
	T <u>28N</u> R <u>1E</u>	<u>K-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
At 8:44 o'clock A M
Date Dec 14 19 93
Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 (K-11) Cor. Comm. to Sec's 25-26-35 & 36. (K-12) ¼ Cor. Comm. to Sec's 35 & 36.
 Orig. Cor. set by W.R. Coon Dec. 1839. Orig. Cor. set by W.R. Coon Dec. 1839.
 Y. Pine 14-N27E-30 Y. Pine 12-S9E-5
 Y. Pine 6-S27W-54 Y. Pine 18-N9W-17
 Cor. set by Seeley Survey 1915. Cor. set by Seeley Survey 1915.
 Survey by G. Henning 7-8-1943. Survey set by G. Henning 7-8-1943.
 Consumers Power Com. Survey Oct. 1967. Consumers Power Com. Survey Oct. 1967.
 DNR Survey Sec. 25.
 Act 74 by Ken Ostling L. 1, P. 173.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (K-11) Cor. Comm. to Sec's 25-26-35 & 36. (K-12) ¼ Cor. Comm. to Sec's 35 & 36.
 Fnd. 1¼" pipe. Fnd. 1" Pinched Pipe.
 N 81° E 15" J. Pine 38.83' NBT (G. Henning)

Peer Group approved as a careful and faithful establishment of the position of the corner.

Note: Previous Co. Surveyors have indicated that the original Twp. ^{SUB.} notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (K-11) Cor. Comm. to Sec's 25-26-35 & 36. (K-12) ¼ Cor. Comm. to Sec's 35 & 36.
 Fnd. 1¼" pipe. Set Co. Mon.
 N 25° E 16" J. Pine 25.18' N 42° W 15" Maple 56.70'
 S 65° E 20" J. Pine 50.17' N 50° E 12" Maple 48.65'
 S 15° E 9" Oak 41.85' N 80° E 15" J. Pine 38.83' NBT
 S 40° W 10" Oak 31.82' S 33° E 12" Maple 27.96'

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E Marlatt Date 12-13-1993

Surveyor's Michigan License No. 18660

