

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in OSCEOLA

23 pg 194

| <u>Osceola</u><br>(County)            | Located In:              | Corner Code # |
|---------------------------------------|--------------------------|---------------|
| 1. Public Land Survey                 | T <u>28N</u> R <u>1E</u> | <u>K-11</u>   |
|                                       | T <u>28N</u> R <u>1E</u> | <u>K-12</u>   |
|                                       | T _____ R _____          | _____         |
|                                       | T _____ R _____          | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____         |
|                                       | S _____ T _____ R _____  | _____         |

**FILED**  
 At 8:44 o'clock A M  
 Date Dec. 14 19 93  
 Clerk/Register of Deeds  
 Osceola County, Michigan  
 Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Donald E. Marlatt, in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|   |   |
|---|---|
| (K-11) Cor. Comm. to Sec's 25-26-35 & 36.<br>Orig. Cor. set by W.R. Coon Dec. 1839.<br>Y. Pine 14-N27E-30<br>Y. Pine 6-S27W-54<br>Cor. set by Seeley Survey 1915.<br>Survey by G. Henning 7-8-1943.<br>Consumers Power Com. Survey Oct. 1967.<br>DNR Survey Sec. 25.<br>Act 74 by Ken Ostling L. 1, P. 173. | (K-12) ¼ Cor. Comm. to Sec's 35 & 36.<br>Orig. Cor. set by W.R. Coon Dec. 1839.<br>Y. Pine 12-S9E-5<br>Y. Pine 18-N9W-17<br>Cor. set by Seeley Survey 1915.<br>Survey set by G. Henning 7-8-1943.<br>Consumers Power Com. Survey Oct. 1967. |
|---|---|

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

|  |  |
|--|--|
| (K-11) Cor. Comm. to Sec's 25-26-35 & 36.<br>Fnd. 1 ¼" pipe. | (K-12) ¼ Cor. Comm. to Sec's 35 & 36.<br>Fnd. 1" Pinched Pipe.<br>N 81° E 15" J. Pine 38.83' NBT (G. Henning). |
|--|--|

Peer Group approved as a careful and faithful establishment of the position of the corner.

Note: Previous Co. Surveyors have indicated that the original Twp. <sup>SUB.</sup> notes are fraudulent.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

|   |   |
|---|---|
| (K-11) Cor. Comm. to Sec's 25-26-35 & 36.<br>Fnd. 1 ¼" pipe.<br>N 25° E 16" J. Pine 25.18'<br>S 65° E 20" J. Pine 50.17'<br>S 15° E 9" Oak 41.85'<br>S 40° W 10" Oak 31.82' | (K-12) ¼ Cor. Comm. to Sec's 35 & 36.<br>Set Co. Mon.<br>N 42° W 15" Maple 56.70'<br>N 50° E 12" Maple 48.65'<br>N 80° E 15" J. Pine 38.83' NBT<br>S 33° E 12" Maple 27.96' |
|---|---|

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E. Marlatt Date 12-13-1993  
 Surveyor's Michigan License No. 18660

