

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Oscoda (County)	Located In:	Corner Code #
1. Public Land Survey	T 28N R 1E T 28N R 1E T _____ R _____ T _____ R _____	M-9 M-10 _____ _____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____ _____

L 3 Pg. 204

FILED  
At 8:54 o'clock A M  
Date Dec. 14 19 93

Clerk/Register of Deeds  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald E. Marlatt in a field survey on December 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(M-9) S.E. Cor. Sec. 24. Original Cor. set by Lewis Clawson Dec. 1839. Y. Pine 25-S74W-24 Y. Pine 26-N70W-28 Recovered & renewed by G. Henning in 1930's. DNR Survey Sec. 30, 28-2, June 1969. Land Cor. Rec. by Ken Ostling L. 2, P. 297. DNR Survey Sec. 25. Survey in Sec. 30, 28-2, by N.C. Caldwell 5-4-1974.	(M-10) E 1/4 Cor. Sec. 25. Original Cor. set by Lewis Clawson Dec. 1839. Y. Pine 30-S58W-46 Y. Pine 26-N15W-65 DNR Survey Sec. 30, 28-2, June 19 DNR Survey Sec. 25. Survey in Sec. 30, 28-2, by N.C. Caldwell 5-4-1974.
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(M-9) S.E. Cor. Sec. 24 Fnd. Co. Mon. S 45° W 12" Oak 61.6' Ex.	(M-10) E 1/4 Cor. Sec. 25. Fnd. Co. Mon. R.T. Post 40' East N 49° E 16" N. Pine 35.65' Ex. S 76° E 14" W. Pine 23.88' Ex. N 60° W 24" Oak 40.58' Ex.
---	---

Peer Group approved (M-9) as a perpetuation of the original government corner.  
Peer Group approved (M-10) as the best available evidence of the re-establishment of the original corner.

Note: Previous Co. Surveyors have indicated that the original Twp. <sup>SUB.</sup> notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(M-9) S.E. Cor. Sec. 24. Co. Mon. S 45° E 15" Oak 58.73' S 45° W 12" Oak 61.60' N 48° E 14" Oak 50.29' S 83° E 9" Oak 39.80'	(M-10) E 1/4 Cor. Sec. 25. Co. Mon. N 49° E 16" N. Pine 35.65' S 76° E 14" W. Pine 23.88' S 61° W 16" Oak 51.16' N 60° W 24" Oak 40.58'
---	--

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E. Marlatt

Date 12-13-1993

Surveyor's Michigan License No. 18660

