

Montmorency County Remonumentation

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| | | | |
|--|--------------------------|---------------|--|
| <u>Oscoda</u> <small>(County)</small> | Located in: | Corner Code # | |
| 1. Public Land Survey | T <u>28N</u> R <u>1E</u> | <u>L-13</u> | |
| | T <u>28N</u> R <u>1E</u> | <u>M-13</u> | |
| | T _____ R _____ | _____ | |
| | T _____ R _____ | _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | |
| | S _____ T _____ R _____ | _____ | |

L 3 pg 199

FILED

At 8:49 o'clock A M.

Date Dec. 14 1993

Clerk/Register of Deeds
Oscoda County, Michigan
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Donald E. Marlatt, in a field survey on December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| | |
|--|---|
| <p>(L-13) S. $\frac{1}{4}$ Cor. Sec. 36. Original Cor. set by Lewis Clawson 1839. Y. Pine 4-N32W-2.05' Y. Pine 30-N67-E-70' Consumers Power Co. Survey Oct. 1967.</p> | <p>(M-13) S.E. Cor. Sec. 36. Original Cor. set by Lewis Clawson 183 Y. Pine 22-S66W-93' Y. Pine 22-N15E-64' DNR Survey in Sec. 31, T28N, R2E. Consumers Power Co. Survey Oct. 1967.</p> |
|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

| | |
|---|---|
| <p>(L-13) S. $\frac{1}{4}$ Cor. Sec. 36. Fnd. no evidence of Cor. Set Co. Mon. single. Proportion on S. line Sec. 36. Distance matched Consumers Power Co. Survey.</p> | <p>(M-13) S.E. Cor. Sec. 36. Fnd. 1$\frac{1}{2}$" bar buried 18" (reaper shaft Intersection of Townline & Nancy Brown Rds.</p> |
|---|---|

L-13 Peer group approved as the careful and faithful establishment of the position of corne
M-13 Peer Group approved as a perpetuation of the original government corner.

Note: Previous Co. Surveyors have indicated that the original Twp. ^{sub.} notes are fraudulent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

| | |
|--|---|
| <p>(L-13) S. $\frac{1}{4}$ Cor. Sec. 36. Co. Mon. N 75° E 14" Oak 58.90' S 29° E 13" W. Pine 54.25' S 20° W 23" N. Pine 63.30' N 88° W 14" Oak 41.91'</p> | <p>(M-13) S.E. Cor. Sec. 36. 1$\frac{1}{2}$" bar. N 64° W 13" W. Pine 51.10' N 25° W 13" W. Pine 62.61' S 56° E 10" Oak 65.0' S 53° W 16" N. Pine 42.19'</p> |
|--|---|

Note: Witnesses marked with 30 penny spikes & I.D. tag #18660.

Signed by Donald E. Marlatt
Surveyor's Michigan License No. 18660

Date 12-13-1993

