

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

MONTMORENCY &  
OSCODA COUNTY


T 28 & 29 N R 2 & 3 E

DESCRIPTION OF CORNER Twp. corner common to Sections 1-6-31-36

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 5-20-71

WITNESSES TO CORNER..... MSHD 14" R. Pine S 72 W 72.0'



MSHD 7" J. Pine N 69 W 59.1'

4" Tw. Red Pine N 56 E 55.5'

AND

24" W.P. Stp N 61 E 144.7'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by E. Houghton in the Mid 1930s. He calls it Seeley's Town corner. Iron fish plates and stones on corner. Two Hem. O.B.s in Place. Took NBT 24" W.P. Stp N.E. Schaaf replaced said fish plates with iron pipe in block of concrete. Found & rewitnessed by MSHD around 1960. We replaced Schaaf's pipe with Dept. Mon.

SURVEYOR'S SEAL

SIGNED *Anneth Westling* DATE 5-27-71  
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68