

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY  
T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Section 25-26-35-36

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 12-3-69

WITNESSES TO CORNER..... 8" J. Pine N 50 E 3.4'



12" R. Oak S 45 W 25.5'

6" S. Maple N 15 W 32.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a retracement in this township. Found 1-1/2" pipe in concrete as established by 1935 Schaaf survey, whose record claimed to identify stumps of the USBTs.

Fits good for measurements returned by the U. S. examination of these lines, and very likely is a restoration of the U. S. corner. This corner is over 7 chains North of a normal location, which results in severe distortion of the four surrounding sections.

SURVEYOR'S SEAL

SIGNED

*Verne A. ...*

DATE

12-10-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR #10068

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68