

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY
T 28 N R 2 E

DESCRIPTION OF CORNER 1/4 corner common to Sections 17-20

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 12-23-69

WITNESSES TO CORNER..... * 5" R. Oak S 75 E 52.1'



* 7" J. Pine N 63 E 66.7'

7" R. Oak N 34 W 73.6'

AND * N. C. Caldwell Witnesses, remarked

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a retracement in this area. Found pipe as established in 1935 Schaaf survey at corner. Subsequently used in adjacent section subdivision by local survey. Seeley's corner falls some 8-9' SW, but was apparently disregarded in Schaaf survey. No conclusive evidence for either corner, but feel our location conforms to most recent usage, and some property delineation based on it.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Kevin J. O'Neil

DATE

12-29-69

REGISTERED LAND SURVEYOR #T0068

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68