

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY
T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Sections 16-17-20-21

CORNER MONUMENT Left 1-1/2" pipe in place

DATE MONUMENT PLACED AND WITNESSED 12-23-69

WITNESSES TO CORNER..... * 14" Y Pine stp N 07 E 42.1'



* 18" Y. Pine stp N 55 W 162.4'

* 14" J. Pine S 07 W 112.1'

AND N.C. Caldwell Witnesses

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

THIS CORNER WAS RECOVERED DURING A RETRACEMENT IN THIS TOWNSHIP. FOUND 1-1/2" PIPE AT CORNER WHICH MARKS POSITION ESTABLISHED BY C.O. SEELEY IN 1916 SURVEY. CORNER USED BY HENNING IN 1933, AND PERPETUATED BY N.C. CALDWELL IN 1963. THIS CORNER APPEARS SOMEWHAT OUT OF POSITION WITH REGARD TO E-W MEASUREMENT TO ADJACENT CORNERS. HOWEVER, IN VIEW OF ITS LONG STANDING, ITS CONTROL FOR ADJACENT OCCUPATION, ITS USE BY TWO OR MORE SUBSEQUENT SURVEYS, AND ITS GENERAL ACCEPTANCE, THIS POSITION MUST BE HONORED AS THE MOST ACCEPTABLE LOCATION FOR THIS CORNER.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED *Kenneth J. Oetting* DATE 12-29-69
REGISTERED LAND SURVEYOR #10068

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68