

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY
T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Sections 8-9-16-17

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 11-5-69

WITNESSES TO CORNER..... 12" J. Pine N 4 W 3.9'



10" J. Pine N 62 E 54.5'

10" J. Pine S 20 E 34.2'

AND

N. C. Caldwell Witnesses

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a retracement in this area. Found 1½" pipe with concrete base in place, as established in 1936 survey by Marcus Schaaf, whose record claims sites of the U.S.B.T.s. Accepted reluctantly because of disproportionate measurements East and West. However, this corner was used in subdivision of Section 17, and believe used to identify parcels in Sec. 16, and, further, can find no conclusive support for any other position.

SURVEYOR'S SEAL

SIGNED *Kimberly J. Ostling* DATE 11-12-69
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68