

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES
LAND CORNER RECORD


OSCODA COUNTY
T 28 N R 2 E

DESCRIPTION OF CORNER 1/4 corner common to Sections 26 - 27

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 12-22-69

WITNESSES TO CORNER.....



7" W. Pine N 73 E 24.2'

7" R. Pine N 47 W 5.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement during a survey in this area. Schaaf corner was about 30' West, but could find no positive evidence for this location, which placed 1/4 corner 30' out of line between section corners.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Penwith J. Ostling
REGISTERED LAND SURVEYOR 10068

DATE

12-29-69

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68