

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY  
T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Secs. 23-24-25-26

CORNER MONUMENT Set Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 12-23-69

WITNESSES TO CORNER..... 1" R. Pine S 22 W 7.9'



1" R. Pine N 62 E 2.3'

10" B. Cherry S 86 W 95.9'

AND 9" B. Cherry S 18 E 55.8'

Fe Cor N 68 E 59'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was recovered during a retracement in this township. Found C. O.

Seeley stake bottom, as established in early 1900 survey, from his record.

Nothing else evident. Other corners referenced to this position, and considered best available evidence for corner.

SURVEYOR'S SEAL

SIGNED

*Ernest H. Oetting*

DATE

12-29-69

DISTRIBUTION:

REGISTERED LAND SURVEYOR #10068

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68