

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

OSCODA COUNTY


T 28 N R 1 E  
T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Sections 24-25-19-30

CORNER MONUMENT Left 1" iron, raised with 1/2" rebar, in place

DATE MONUMENT PLACED AND WITNESSED 6-3-70

WITNESSES TO CORNER.....



Spike in 7" Oak S 50 E 53.6

\* 12" B. Oak S 41 W 61.4

AND

\* Henning 1930 Witness

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey in this area. Found iron bar as restored by Henning in 1930 from previous evidence, and used by him in more recent survey of Sec. 30. Probably perpetuates Randall corner. Schaaf monument was found about 2' NE and was removed to avoid confusion.

SURVEYOR'S SEAL

SIGNED *Pennington* DATE 7-7-70  
REGISTERED LAND SURVEYOR 10068

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68