

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

OSCODA COUNTY


T 28 N R 2 E

DESCRIPTION OF CORNER Sec. corner common to Sections 3-4-9-10

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 12-14-70

WITNESSES TO CORNER..... 10" J. Pine N 40 E 16.45'



5" R. Pine N 43 W 71.8'

9" J. Pine S 67 W 13.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during retracement survey in this township. Found wood post bptton at corner, apparently placed in a survey prior to 1935 CCC surveys. This corner previously located about 1958 during a corner search. Two old NBTs facing this location.

SURVEYOR'S SEAL

SIGNED

Quintin Wilkey
REGISTERED LAND SURVEYOR 10088

DATE

12-21-70

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68