

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 2 E


OSCODA COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 21-22-27-28

CORNER MONUMENT Left "T" rail in place below surface

DATE MONUMENT PLACED AND WITNESSED 5-20-69

WITNESSES TO CORNER.....



5" W. Pine S 84 W 27.6'

10" R. Pine S 55 E 97.8'

AND

6" J. Pine N 37 E 72.9'

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during survey in this township. Found 2½" T iron in place as established by C. O. Seeley about 1916. His record claims definite identification of U. S. bearing tree from which he reestablished corner.

Schaaf 1½" pipe in concrete was found about 8.8' South and 22.2' East of Seeley's and was removed to eliminate confusion. Could not ignore Seeley testimony at this point.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Wetling
REGISTERED LAND SURVEYOR 10068

DATE 6/9/69