

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 2 E


OSCODA COUNTY

DESCRIPTION OF CORNER Sec. corner common to Sections 27-28-33-34

CORNER MONUMENT Left "T" rail in place below surface

DATE MONUMENT PLACED AND WITNESSED 5-20-69

WITNESSES TO CORNER..... 8" J. Pine N 87 W 14.5'



5" R. Pine S 68 E 131.8'

* 22" R. Pine S 15 E 136.3'

AND

* Old NBT by C. O. Seeley

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found during a survey in this township. Found Seeley's T iron in place as established in 1916 survey. Apparently no positive evidence was found by Seeley, and his established corner provides best distribution of lands affected by this corner.

Schaaf pipe is about 24.6' South and 7.4' W. of Seeley's.

SURVEYOR'S SEAL

SIGNED *Levitt Helling* DATE 6/9/69
REGISTERED LAND SURVEYOR 10068