

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 2 E


OSCODA COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 33 & 34

CORNER MONUMENT Drove 1 1/2" pipe, 20" long below surface

DATE MONUMENT PLACED AND WITNESSED 5-20-69

WITNESSES TO CORNER.....



6" R. Pine N 62 W 21.50'

6" R. Pine N 62 E 21.65'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners. No original evidence. Schaaf pipe removed from a point 12.5' South and 7.4' West of our location.

SURVEYOR'S SEAL

SIGNED *Anneth Pettig* DATE 6/9/69
REGISTERED LAND SURVEYOR 10068