

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 2 E


OSCODA COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 27 & 28

CORNER MONUMENT Drove 1 1/2" x 20" pipe below surface

DATE MONUMENT PLACED AND WITNESSED 5-20-69

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" R. Pine S 63 E 70.1'

8" R. Pine N 40 E 119.4'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement, midpoint on line, between section corners. No original evidence. Schaaf pipe was 16.6' South and 5' East, and was removed to avoid confusion.

SURVEYOR'S SEAL

SIGNED Kenneth Wetling DATE 6-9-69
REGISTERED LAND SURVEYOR 10068