

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


OSCODA COUNTY  
T 28 N R 2 E

DESCRIPTION OF CORNER 1/4 Corner common to Sections 25 - 26

CORNER MONUMENT Set Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 12-22-69

WITNESSES TO CORNER..... \_\_\_\_\_



13" Oak S 35 W 59.6'

13" Oak S 78 W 52.2'

AND \_\_\_\_\_

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored by proportionate measurement, according to measurements returned by the government examination of this, and other, lines in this township. The U. S. examination found the original corner to sections 25-26-35-36 over 7 chains North of a normal location, resulting in distorted sectional protraction of these four sections.

SURVEYOR'S SEAL

SIGNED *Leunith J. Pettig* DATE 12-29-69  
REGISTERED LAND SURVEYOR #X0068

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing