

**SURVEY &  
REMONUMENTATION**

MAR 19 1997

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

*Liber 4 pg 157*

For corners in Oscoda (County) Located in: Corner Code #

1. Public Land Survey	T <u>27N</u> R <u>2E</u>	<u>M - 1</u>
	T <u>27N</u> R <u>3E</u>	<u>A - 1</u>
	T <u>28N</u> R <u>2E</u>	<u>M - 13</u> ✓
	T <u>28N</u> R <u>3E</u>	<u>A - 13</u>
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Section	S ___ T ___ R ___	___
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
OSCODA COUNTY  
FILED

26 NOV 96 3:13 P.M.

PATSY J. PETERS  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Marvin E. Myers, in a field survey on June 28, 19 96  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE:** Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO Lewis Clason May 1839 Mon.-(A)Established cor. of Twps. 27 & 28 North, Ranges 2 & 3 East WIT: (1)4" Spruce Pine S27°W 50 lks. (2)14" dry Pine stub N60°W 44 lks. (3)18" dry Pine stub S51°E 65 lks.	Norm Caldwell Date Unknown Mon.-(B)R.R. Rail Kenneth Ostling Nov. 1968 Mon.-Fd. (B)	MDOT Notes Nov. 13, 1968 Mon.-Fd. 2" wood peg Placed 1"x2" stake WIT: 10" J.Pine N45°W 41.00' 12" J.Pine S55°E 45.15' 20" Norway N55 86.39'
--	--	--

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found cabin spike in North track of E-W  
Found DNR witness post North 9.00' as stamped  
Found Blaze 24" Norway N60°E 85.7' to blaze  
Found 1/2" x 24" Bar 9" below surface  
And is accepted as the best available evidence of the position of the original corner  
Township corner common to T27 & 28 N, R2 & 3E

**APPROVED**  
County Remonumentation  
Peer Review Group

*Nov 16 Nov 96*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed standard Oscoda County Monument in North track of E-W Trail Road at record post  
WIT: Set nail W. side 12" J.Pine N10°W 33.92'  
Set nail S. side 24" Norway N60°E 86.99'  
Set nail S. side Cherry N75°E 31.70'  
Intersection of roads S77°E 123'±  
Set nail E. side 2" Poplar S05°W 17.11'



Signed by Marvin E. Myers Date Sept 2, 1996  
Surveyor's Michigan License No. 31600