

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In:			
Oscoda (County)	Located In	Corner Code #	
1. Public Land Survey	T <u>28N</u> R <u>2E</u>	<u>L-7</u>	
	T _____	_____	_____
2. Property Controlling in Section	S <u>24</u> T <u>28N</u> R <u>2E</u>	<u>4</u>	
	S _____ T _____	R _____	_____
3. Miscellaneous Property in Section	S _____ T _____	R _____	_____
	S _____ T _____	R _____	_____
4. Lot No: _____	Recorded Plat: _____		
5. Private Claims: _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl T. Kiiskila, in a field survey on December 3, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-7 G.L.O. William R. Coon D.S. 1839 set quarter section post
 Wit: Spruce Pine 5" N21°W 7 links
 Spruce Pine 6" S24°E 23 links

4- Norman C. Caldwell R.L.S. # 12018 set the Southeast corner of the Northwest quarter of the Northwest quarter of section 24 while doing the Assessor's Plat of the Hill Settlement.

1969 Kenneth J. Ostling R.L.S. #10068 found a 1 1/4" pipe for corner previously set by Seeley in 1916.
 No witnesses were given.

Norman C. Caldwell R.L.S. #12018 shows a standard county corner on his Assessor's Plat of the Hill settlement, April 1978.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

L-7 Found a standard county monument fitting the Assessor's Plat of the Hill Settlement.

4- Found a concrete monument fitting the Assessor's Plat of the Hill Settlement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-7 Found a standard county monument

4- Found a concrete monument

Wit: Steel fence post S61°E 45.50'
 10" J. Pine S11°W 46.08'
 8" R. Pine S72°W 74.32'
 P. Pole N48°E 40.20'
 Centerline of East-West road.

Wit: SW corner of cabin N26°E 43.5'
 14" W. Pine S66°E 18.28'
 8" Cherry S26°W 59.21'
 Conc. Monument S81°E 6.72'
 Carsonite post North 1±

Signed by: _____

Carl T. Kiiskila

Date: _____

3-12-03

Surveyor's Michigan License No.: _____

33981

