

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: _____ Located In _____ Corner Code # _____
 Oscoda _____
 (County)

1. Public Land Survey T _____ R _____
 T _____ R _____
 2. Property Controlling in Section S 24 T 28N R 2E 5
 S 24 T 28N R 2E 1
 3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on December 3, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

5- Norman C. Caldwell R.L.S. #12018 set the Northeast corner of the Southwest quarter of the Northwest quarter of section 24 while doing the Assessor's Plat of the Hill Settlement.

1- Norman C. Caldwell R.L.S. #12018 set the Northeast corner of the Northwest quarter of the Northwest quarter of section 24 while doing the Assessor's Plat of the Hill Settlement.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

5- Found 1/2" concrete monument fitting the Assessor's Plat of the Hill Settlement.

1- Found 1/2" rered fitting the Assessor's Plat of the Hill Settlement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

5- Found a Concrete monument

Wit: Steel fence post	N68°E	.83'
8" Poplar	S32°E	9.85'
12" Poplar	S52°W	43.94'
2" Cherry	N08°W	8.05'
Wooden Post	SW	1'±

1- Found 1/2" rered

Wit: 10" Jack Pine	N28°W	62.91'
P. Pole	N39°E	40.68'
12" Oak	S59°E	34.67'
16" Oak	S51°W	39.87'

Signed by:

Carl T. Kiiskila

Date:

3-12-03

Surveyor's Michigan License No.:

33981

