

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 28 N.R. 3 E


Oscoda COUNTY

DESCRIPTION OF CORNER 1/4 corner on South Side Sec. 32

CORNER MONUMENT Set Cons. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 11/7/68

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

8" R. Oak N 65 W 29.1'

6" R. Oak N 15 E 15.4'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement, midpoint on line, between standard corners of Section 32. Unable to identify conclusive evidence of U.S. corner or any previous corner.

SURVEYOR'S SEAL

SIGNED *Levath Ostling* DATE 11/27/68
REGISTERED LAND SURVEYOR
#10068