

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 28 N.R. 3 E


Oscoda COUNTY

DESCRIPTION OF CORNER 1/4 corner on South side Sectbn 31

CORNER MONUMENT Set. Cons. Dept. Mon.

DATE MONUMENT PLACED AND WITNESSED 11/7/68

WITNESSES TO CORNER.....



8" R. Pine N 16 W 55.3'

8" R. Pine N 60 E 21.0'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by proportionate measurement between standard corners of this section, a 3/4" pipe at a fence corner is located about 74' feet west and 83' South of our corner, but this appears to have been established without sufficient knowledge of other controlling corners, for the purpose of wiring hunting lands. Could find no support for accepting said location as the proper position for corner, and it was disregarded in this survey.

SURVEYOR'S SEAL

SIGNED *Kenneth Ostling* DATE 11/27/68  
REGISTERED LAND SURVEYOR #10068