

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>28</u> <sup>N.</sup> <input checked="" type="radio"/> , R. <u>3</u> <sup>E.</sup> <input checked="" type="radio"/>	C-6; C-7; D-7
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ <sup>N.</sup> <input type="radio"/> , <sup>S.</sup> <input type="radio"/> R. _____ <sup>E.</sup> <input type="radio"/> , <sup>W.</sup> <input type="radio"/>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ <sup>N.</sup> <input type="radio"/> , <sup>S.</sup> <input type="radio"/> R. _____ <sup>E.</sup> <input type="radio"/> , <sup>W.</sup> <input type="radio"/>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on December 18, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- C-6 Reset this corner M.P.O.L. to conform to new position for 17-18-19-20.
- C-7 Set at stake bottom concluded to be E. P. Albertson's restoration of U. S. corner in 1900. One Albertson witness in place.
- D-7 Set corner by proportionate measurement between section corners, to conform with new position for corner to 17-18-19-20.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6	C-7	D-7
Set DNR monument	Set DNR monument	Set DNR monument
8" Birch N45°E 9.55	8" R. Pine S75°W 2.70	7" Maple S57°E 7.4
6" Maple N33°W 11.55	6" R. Pine S80°E 12.45	7" Birch S30°W 12.15

SIGNED BY *Kenneth J. Ostling* DATE \_\_\_\_\_  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

OSCODA COUNTY