

SURVEY & REMONUMENTATION

Liber 4 Pg 119

MAR 19 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
OSCODA COUNTY
FILED

For corners in OSCODA **COMMISSION**
(County)

Located In:

Corner Code #

17 SEP 96 9:49 A.M.

PATSY J. PETERS
REGISTER OF DEEDS

LIBER 196 PAGE 5704

Register of Deeds Stamp & File Number

1. Public Land Survey	T	28N	R	4E	H-1
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Larry G. Beauregard, in a field survey on July, 19 96 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


H-1 North $\frac{1}{4}$ corner Section 3.

No corner set on original survey.

No Act 74 recorded.

No Act 132 recorded.

No corner found.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I set an Oscoda Co. std corner, 3" brass cap on a 1" x 3' pipe by single proportion on Co. line and in line with old hunting wire laying on the ground.

This corner is 11.57' East of std. corner S. $\frac{1}{4}$ corner Section 34, T 29N, R 4E and 18.5'± North of a E & W barbwire fence line.

APPROVED
County Remonumentation
Peer Review Group

NCC
9 SEPT 96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

North $\frac{1}{4}$ corner Section 3

Oscoda Co. std. corner 3" brass cap on a 1" x 3' pipe. Accepted as a careful and faithful establishment of the position of the corner. Approved by the Peer Group on July 12, 1996.

West 11.57' conc. mon. std. cor. Sec. 34, T 29 N, R 4 E.

N 40° W 19.22' 10" June Berry in clump of three

North 84.58' 20" R. Oak

S 05° E 63.65' 15" R. Oak

S 65° E 96.10' Top of wood gate post (PK nail & PS tag 18654)

Placed 60d penny spike and P.S. tag #18654 (typ)

Signed by Larry G. Beauregard

Date 9-4-1996

Surveyor's Michigan License No. 18654