

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

CORNER RECORD

T 29 NR 1 W
T 30 NR 1 W

----- Otsego ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4-5-32-33

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap
($\frac{1}{2}$ " iron bar here also)

WITNESSES TO CORNER 7" W. Oak - N38E - 59 $\frac{1}{2}$ links

7" R. Oak - N63W - 42 links

9" R. Oak - S65W - 38 $\frac{1}{2}$ links

* 18" W. Pine stump - S80E - 86 $\frac{1}{2}$ links

* G.F.DeLaMater witness 1926

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was previously restored from the government BTs by G.F.DeLaMater, Otsego County Surveyor, in 1926. Corner was remonumented and witnessed by Forestry Division Land Surveyor to perpetuate a government corner and make for easier identification of state land boundaries. Stumps of three government BTs still in place.

Corner was placed and witnessed April 27, 1959.

SURVEYORS SEAL

SIGNED *Kenneth J. Petting* DATE 4/28/59
REGISTERED LAND SURVEYOR