

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 N.R. 1 W


Otsego COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 28-29

CORNER MONUMENT Set Cons. Dept. Monument

DATE MONUMENT PLACED AND WITNESSED 5/7/68

WITNESSES TO CORNER.....



CIRCLE CORNER REGISTERED

5" J. Pine N 7 E 5.6'

9" J. Pine S 54 W 26.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by proportionate measurement between section corners. Nothing left for U.S. evidence. Two other pipes were found in vicinity, a 3/4" pipe S 65E 30.0' and a 1" pipe S 54 E 20.6' from our location. These are believed placed by land owners at temporary points of our survey.

SURVEYOR'S SEAL

SIGNED *Kenneth J. Bithing* DATE 6/27/68
REGISTERED LAND SURVEYOR #10068