

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Otsego (County)	Located In	Corner Code #
1. Public Land Survey	T _____ R _____	_____
2. Property Controlling in Section	T _____ R _____	_____
	S 16 T 29N R 1W	4
	S 16 T 29N R 1W	9
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiskila, in a field survey on September 6, 2007 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

4- This corner position was not established during the original Government survey.

9- This corner position was not established during the original Government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

4- Established the Northwest corner of the Southeast quarter of the Northeast quarter of section 16 as per B.L. M. instructions for the subdivision of a section.

9- Established the Southeast corner of the Southwest quarter of the Northeast quarter of section 16 as per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4- Set 5/8" X 32" Rerod with P.S. cap #33981  
 Wit: Set nail and tag in NE side of a 8" Maple N40°W 22.61'  
 Set nail and tag in SE side of a 11" Red Pine N45°E 53.45'  
 Set nail and tag in SW side of a 19" Red Pine S37°E 19.75'  
 Set nail and tag in N side of a 22" Red Pine S71°W 17.88'  
 Set blue Carsonite post North 1'±

9- Set 5/8" X 32" Rerod with P.S. cap #33981  
 Wit: Set nail and tag in S. side of a 5" Red Pine N36°W 4.44'  
 Set nail and tag in NW side of a 5" Jack Pine S69°W 16.01'  
 Set nail and tag in W. side of a 9" Jack Pine S02°E 8.94'  
 Set nail and tag in N. side of a 8" Jack Pine S89°E 12.08'  
 Set blue Carsonite post North 1'±

Signed by: Carl T. Kiskila  
 Surveyor's Michigan License No.: 33981

Date: 9-26-07

