

OTSEGO COUNTY REMONUMENTATION

MAR 17 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Also Act 345, P.A. 1990

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD
99 DEC 27 PM 2:54
EVELYN M. PRATT CLERK / REGISTER OF DEEDS

SECTION

For corners in

Otsego (County) Located In: Corner Code #
1. Public Land Survey T 29N R 1W E-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

4. Lot No. , Recorded Plat
5. Private Claims

I, Ronald C. Brand, in a field survey on October 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

Grid with columns A-M and rows 1-13 for recording stamp and file number.

A. Description of original monument and accessories and/or subsequent restoration:

E-13 Southeast corner Section 32

1839 James Mullett Set post corner of Sections 32 & 33 Pine 6" N9°W 29 links, Pine 8" N51°E 60 links

1856 Resurvey Harvey Mellon at 80.00 chains Set post corner of Sections 4 & 5 on old line & 5.22' West of old corner Spr. Pine 7" N36°E 43 links, Spr. Pine 10" N20°W 30 links

1968 DNR Retracement, Kenneth Ostling, Set Standard Monument from 1914 E.S. Houghton NBT R. Pine 24" S50°E 103.7' (Houghton), R. Pine 6" S50°W, 76.1', R. Pine 7" N60°W 32.5'

1968 S.O. Thorsen, Otsego County Surveyor notes, Liber 3, Page 488, Standard Conservation Dept. monument 1" pipe w/4" cap R. Pine 6" S58°W 76.1', R. Pine 7" N60°W 32.5', R. Pine 24" S50°E 103.7' (Houghton 1914)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13 Southeast corner Section 32

Fd. Standard DNR monument 15' +/- North of centerline trail road Fd. dead 24" R. Pine S50°E 103.6', Fd. 15" R. Pine S60°W 76.23'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13 Southeast corner Section 32

Fd. Standard DNR monument is accepted as a careful and faithful reestablishment of the position of the original corner. Monument is 15' +/- North of centerline trail road and falls on West edge of clear cut area to South Fd. dead 24" R. Pine S50°E 103.6' Set Nail & Tag in blazed 8" J. Pine S23°W 41.80', Set Nail & Tag in 15" R. Pine S60°W 76.23', Set Nail & Tag in 5" J. Pine N20°W 22.02', Set Nail & Tag in blazed 17" R. Pine N61°E 32.76'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Dec. 17, 1999 Date

Chairman

Signed by Surveyor's Michigan License No. 43046



Date 12/22/99