

MAR 17 2000

OTSEGO COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
Also Act 345, PA 1990

OTSEGO COUNTY MICHIGAN  
RECEIVED FOR RECORDING  
99 DEC 27 PM 2:56  
EVELYN M. PRATT  
CLERK / REGISTER OF DEEDS

For corners in

<u>Otsego</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>1W</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, James L. Schwandt, in a field survey on Jan. 19, 1999, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

James Mullett, 1839 Set Post Black Oak, 10" N53°E, 43 links Pine 4", N82°W, 45 links	Kenneth Ostling set Conservation Dept monument below surface 05-06-68 Recorded by S. Thorson 10-29-68 24" R. Pine, N23°W, 45.7' 17" R. Pine, N52°E, 49.3' Set by proportionate measurement	Larry Beaugard #18654, 1986 Found DNR corner N23°W, 43.7', 24" R. Pine N52°E, 49.9', 17" R. Pine
---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Department of Conservation Monument, 1" pipe with brass cap from 1968  
Found 30" R. Pine, N23°W, 45.70' to face  
Found 24" R. Pine, N52°E, 49.3' to face

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Department of Conservation Monument in corner is accepted as a careful and faithful reestablishment of the position of the original corner.  
Spike in found 30" R. Pine, N23°W, 46.41'  
Spike in found 24" R. Pine, N52°E, 50.12'  
P.K. in 8" J. Pine, S33°E, 65.46'  
Face of sign post, N80°W, 46.30'  
Corner is 18.75' North of centerline Highway

Signed by James L. Schwandt  
Surveyor's Michigan License No. 26466



OTSEGO COUNTY REMONUMENTATION  
Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
Date Dec. 17, 1999 [Signature]  
Chairman

Date 12-23-99