

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 29. NR. 2 W. . .

----- Otsego ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 13 & 14 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER -----

20" Wt. Pine Stump - N78E - 76 links -----

10" Aspen - S12E - 36 1/2 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey of Section 13. Both probable original BT stumps in place with possible partial face on SW stump. Found evidence of old stake point when digging. Checks good with pond and marsh crossings north.

Corner was placed and witnessed July 16, 1956

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 7/23/56  
REGISTERED LAND SURVEYOR